

BEAUMONT-CHERRY VALLEY WATER DISTRICT
2017 WATER PIPELINE REPLACEMENT PROJECT
PIPELINE 2 – P-3620-0015

CONTRACT DOCUMENTS

ADDENDUM NO. 1

PLEASE BE ADVISED:

1. **Reference:** Beaumont-Cherry Valley Water District 2017 Water Pipeline Replacement Project, Contract Documents, Bid Form, Bid Schedule 1

Amend the following bid items as follows, to be included in the total Bid Price for Bid Schedule I of the Contract Documents:

ITEM NO.	DESCRIPTION OF ITEMS	EST. QUANTITY	UNIT	UNIT PRICE (FIGURES)	TOTAL AMOUNT
101	Furnish project insurance (not to exceed three <i>two</i> percent (3%) <i>(2%)</i> of the Total Bid Price).	1	L.S.		
105	Furnish all labor and material required for asphalt and concrete removal and replacement at locations indicated on the Construction Plans. <i>At the end of each working day, the pipeline trench shall be backfilled with native material. Final pavement repair for Apple Tree Lane shall be in accordance with Riverside County Ordinance 461. The pavement section shall be 4" HMA over 6" of Class II Base.</i>	6,788	S.F.		
106	Install District furnished 8" cement mortar lined ductile iron pipe <i>and appurtenances</i> , Class 350 to an average depth of 4.25 feet below existing roadway (<i>Apple Tree Lane</i>), including installation of restrained joints as shown on the Construction Plans, installation of Contractor furnished backfill material (or native material, if suitable) and compaction per BCVWD Standard Plate 6-1 (36" min cover).	2,470 1,740	L.F.		

ITEM NO.	DESCRIPTION OF ITEMS	EST. QUANTITY	UNIT	UNIT PRICE (FIGURES)	TOTAL AMOUNT
107	<p>Install all District furnished 8" pipeline appurtenances, including, but not limited to, fittings, valves, adapters, per Construction plans (and disinfection of said materials), including export of native material, installation of Contractor furnished backfill material, compaction, and testing.</p> <p>Install District furnished 8" cement mortar lined ductile iron pipe and appurtenances, Class 350 to an average depth of 4.25 below existing ground (along Oak Glen Road), including installation of restrained joints as shown on the Construction Plans, installation of Contractor furnished backfill (or native material, if suitable) and compaction per BCVWD Standard Plate 6-1 (36" min cover).</p>	± 730	L.S. L.F.		

Bid Items 101, 105, 106, and 107 have been amended as part of ADDENDUM NO. 1. Bid amounts to be included in the total Bid Price for Bid Schedule 1 shall be submitted and consider said Amended Bid Items 101, 105, 106, and 107.

By: _____

Mark B. Swanson, RCE No. 72332

Date: _____

12/14/2022

ADDENDUM NO. 1 ACKNOWLEDGEMENT

Bidder hereby acknowledges receipt of Addendum No. 1 and the incorporation thereof in bid proposal for the Beaumont-Cherry Valley Water District 2017 Water Pipeline Replacement Project, Contract Documents, Bid Form, Bid Schedule 1. This acknowledgement page shall be signed, dated and included with the Bidder's Bid Proposal Packet.

Bidder: _____

By: _____
(Bidder's Authorized Representative)

Date: _____

Title: _____